BRUHAT BANGALORE MAHANAGARA PALIKE

SCHEDULE - B

17

Name of the Work : Construction of Flat form to Raithara Santhe at Singapura in Ward No. 11, (Kuvempunagara) Vidyaranyapura Sub Division.

Sl. No.	Approved Qty.	Description	Unit	Schedule-B Rates KRIDL		
				In Figures	Amount	In Words
1	123.12	Earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, **in ordinary soil** not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods etc complete as per specifications and directions of engineer in charge of the work.	Cum	188.68	23230.28	Rupees One Hundred Eighty Eight and Sixty Eight Paise Only
2	46.44	Providing and laying in position plain cement concrete of **mix 1:4:8 with OPC cement @ 180 kgs with 40mm** and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregares @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	4976.70	231117.95	Rupees Four Thousand Nine Hundred Seventy Six and Seventy Paise Only
3	38.88	Providing and constructing granite / trap / basalt size stone masonry in **foundation with cement mortar 1:6**, stone hammerd dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	4058.74	157803.81	Rupees Four Thousand Fifty Eight and Seventy Four Paise Only
4	29.16	Providing and constructing granite / trap / basalt size stone masonry in **basement with cement mortar 1:6**, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Cum	4814.52	140391.40	Rupees Four Thousand Eight Hundred Fourteen and Fifty Two Paise Only
5	123.12	Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20cms, in depth, compacting each deposited layers by ramming after watering with lead upto 50m, and lift upto 1.5m, including cost of all labour etc complete as per specifications and directions of engineer in charge of the work.	Cum	116.60	14355.79	Rupees One Hundred Sixteen and Sixty Paise Only
6	64.80	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work.	Sqm	97.52	6319.30	Rupees Ninety Seven and Fifty Two Paise Only
7	38.21	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams etc complete as per specifications and directions of engineer in charge of the work.	Cum	6214.78	237466.74	Rupees Six Thousand Two Hundred Fourteen and Seventy Eight Paise Only

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

24/x/16

roved Qty.	Description	Unit	Schedule-B Rates		
			KRIDL		
			In Figures	Amount	In Words
8	2932.50	Fabricating supplying and erecting **M.S. TubulerTruss of span upto 10m** bottom and top member is provided with 50x50x6mm double equale angles, welded back to back and in between top and bottom line, in ereas of mid section is provided with 50x50x6mm equal single angle for vertical and inclined members and at supporting ends 40x40x5mm single angle is provided all the members are weldeded togeher with 6mm gusset plate as per drawing, Nos CBS/SD/K-mantap/9/MND/97. The enter truss is anchored in RCC column buy using 4Nos of M.S anchor bolts at eacth support, with 10mm thick base plate and shoe plate. The work includes cutting, straightening , pacing in position of M.S angle and welding wherever necessary, and applying one of red oxide primer coat to all the members including cost of all materials, labour charges,and higher charges of mechineries for cutting welding, granding and erection equipments, etc complete as per specifications and directions of engineer in charge of the work. kgs	128.26	376122.45	Rupees One Hundred Twenty Eight and Twenty Six Paise Only
9	540.00	Providing Meta color sheet roofing with J or L hooks, bolts and nuts 8mm dia C.I plain and bitumen washers over the existing purlins, rafters and trusses includeing cost of materials, labour, complete as per specifications.etc complete as per specifications and directions of engineer in charge of the work. sqm	1200.00	648000.00	Rupees One Thousand Two Hundred Only
		Total		**1834807.73**	

Signature of the Contractor

EXECUTIVE ENGINEER
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

24/10/16

24/10